

- Time and duration of shut down shall be determined by the Administrator, Division of Water.
- The contractor shall notify all water customers effected by the proposed work At least 24 hours in advance to shut down.
- All bends shall be secured by retaining glands, rodding or other methods as approved by the Engineer to restore main to service as soon as possible. Concrete backing shall then be provided in accordance with Standard Detail L-6310 for over bends and L-6311 for sag bends.
- The relocated lines shall be laid to the new line and grade, tested and disinfected prior to shut down of existing main and connection of the relocated lines to the existing main.
- 5. All water lines shall be disinfected by swabbing with a 5 per cent Hypochlorite solution in accordance with the applicable sections of A.W.W.A. C-601.

STANDARD DETAIL

TYPICAL WATER LINE LOWERING

